



Materials:

Main Upright

4 1/2 " O.D. schedule 40 Pipe, .237" wall

Arm Loops

1 5/8" O.D. schedule 40 pipe, .140 wall

Inground Mount

Extends 12" into ground (or deeper if wanted)

Optional:

Custom

Larger pipe sizes and overall dimensions available

Arm Loops

1 and 3 armloops version available

Finishes

Powder coat

Hot-dipped galvanized

Stainless steel #4 finish